



An Exelon Company

2012 Summer Reliability Meeting

Pennsylvania Public Utility Commission

June 7, 2012

Summer Readiness

- ✓ **Capacity Additions**
 - Major projects and local distribution level projects
- ✓ **Preventative Maintenance Activities**
 - Transmission and Distribution Level completions
- ✓ **Employee Preparations**
 - Training and summer equipment preparations
- ✓ **Event Preparedness**
 - Lessons learned incorporated into summer prep drills this spring
- ✓ **Transmission Preparedness**

Capacity Projects

- ✓ Clay Substation:
 - Add a second 90MVA 230-34 kV Transformer and associated Circuit Breakers, Replace the existing electromechanical protection equipment, with new modern digital equipment.
 - Project Costs = \$12.1 Million
 - Provides additional operational and maintenance flexibility.
 - Improves reliability by eliminating the analog relay protection schemes.
 - The Project was placed into service as scheduled on May 30, 2012.
- ✓ Clay Transmission:
 - Route a new 230kV transmission line along 7 miles of existing right of way into Clay Substation and replace the existing single circuit towers with dual circuit monopole structures.
 - Project Costs = \$26.0 Million
 - Improves system reliability and flexibility to address distribution contingencies for Clay and the combination of Clay and Jennersville Substations.
 - The new poles are in place and the second transmission line is scheduled to be in service by June 1, 2013.
- ✓ Center Point 500kV Substation
 - Construct a new 500kV to 230kV substation in Worchester Township, PA in the PECO ROW at the intersection of the 220-79 and 5029 lines.
 - Project Costs = \$50 Million
 - Alleviates the recognized overloads, while further diversifying the geographic locations of the region's 500kV-230kV transformer capacity.
 - Substation was energized and put into service May 2011.
- ✓ Chichester Substation 9B Transformer and Reactor Addition Project
 - Supports the retirement of the Eddystone Unit 2 coal fired generating station as of May 2012.
 - Addition of a new 336MVA transformer in parallel with the existing 9 Transformer with series reactors installed on the combined 132kV secondary of both transformers.
 - Project Costs = \$6.9 Million
 - The Project was placed into service as scheduled on April 30, 2012.

PECO Keys to Success

- ✓ **Reliability Enhancement Programs**
 - Top Priority Circuit Program (TPC)
 - 5% circuits are reviewed every year.
 - Distribution Sectionalizing Program
 - Center City Upgrades
- ✓ **Preventative Maintenance Programs**
 - Vegetation Management Program
 - Circuit Patrols and Thermography
 - Center City Network Inspections
 - Recloser Inspections
 - Manhole Inspections
- ✓ **Capacity Planning**
 - Summer Readiness
 - Analyze all circuits and previous summer performance
 - Issue designs for projected overloads

Storm Preparations

- ✓ Initiate pre-event planning and preparations
- ✓ Secure additional personnel for assistance with restoration and tree trimming
- ✓ Conduct interviews and briefings with media to discuss storm preparations, planning and customer outage expectations
- ✓ Conduct outreach with elected officials and local governments
 - State Regulatory and Elected Officials
 - County 911 Centers Outreach and Staffing
 - Municipal and County Governments

Event Preparedness: Hurricane Irene Lessons Learned

✓ Successes

- Utilization of Established Hurricane Plan
- Advanced Planning
- Staging of Crews
- Communications to Employees


✓ Opportunities for Improvement

- Road Closures
- Customer Communications Regarding Restorations
- Truck Permitting for Foreign Crews

APPENDIX

Reliability Overview

- ✓ Continued strategic investment in infrastructure – capital budget of over \$2.3 billion for the period of 2011-2015.
- ✓ Reliability programs are the keys to success
 - Recloser Performance
 - Vegetation Management
 - Top Priority Circuit (TPC)
- ✓ Despite intense weather in 2011, reliability is very good.
- ✓ As the February 2nd 2011 ice storm which affected 9.7% of PECO customers has rolled off the 12 month rolling indices, SAIFI, CAIDI and SAIDI are below their respective benchmarks and standards established on May 7, 2004.



2011 Review

2011 Storms

- PECO had 9 storms in 2011 including Hurricane Irene on August 27 and a snow storm on October 29.
- 367,000 storm customer interruptions in the 1st quarter of 2011 was the highest 1st quarter value in PECO history.
- February 2011 was the worst February on record for storms.
- The February 2nd ice storm affected 9.7% of PECO's customers with snow depth averaging 6", and icing 1/10 to 1/2" across the PECO territory.

2011 Summer Heat and Rain

- Hot Summer with 6 heat waves – 32 days of 90+ degree heat from May 31 through August 31
- 2001-2010 Average (June 1 through August 31) is 24.1 days of 90+ degrees heat
- July was hottest month in Philadelphia history. 21 days of 90° or more in July, 2011 vs. 19 in July, 2010
- The National Weather Service announced that 2011 was the wettest year in Philadelphia weather history.

Reliability Performance

Rolling 12-month reliability index values through March 2012

	SAIFI	CAIDI	SAIDI
2012 Q1	0.89	111	99
Benchmark	1.23	112	138
Rolling 12 month Standard	1.48	134	198
3-Year Average (2009 – 2011)	1.07	122	131
Benchmark	1.23	112	138
3-Year Average Standard	1.35	123	167

***Performance through March 2012:
SAIFI, CAIDI and SAIDI are all below the PUC Benchmark and Standard***