



An Exelon Company

Richard G. Webster, Jr.
Director
Rates and Regulatory Affairs

Telephone 215.841.4000 ext 5777
Fax 215.847.6208
www.exeloncorp.com
dick.webster@exeloncorp.com

PECO Energy Company
2301 Market Street, S15
Philadelphia, PA 19103

Mail To: 8699
Philadelphia, PA 19101-8699

July 29, 2011

Via Federal Express

Rosemary Chiavetta, Secretary
Pennsylvania Public Utility Commission
Commonwealth Keystone Building
400 North Street
Second Floor
Harrisburg, Pennsylvania 17120

**Re: PUC Docket No. L-00030161
Rulemaking Re Amending Electric Service Reliability Regulations at
52 Pa. Code Chapter 57**

Dear Secretary Chiavetta:

In accordance with Electric Service Reliability Regulations at 52 Pa. Code Chapter 57, enclosed are an original and six copies of PECO's 2011 Quarterly Reliability Report for the period ending June 30, 2011.

Because portions of the report contain sensitive and proprietary information, PECO is filing two versions of the report, one public and one proprietary. PECO requests that the proprietary report, which has been separated and clearly marked with a "Confidential and Proprietary" header on each page, be kept confidential, pursuant to Commission Order of March 20, 2006.

If you have any further questions regarding this matter, please call me at 215-841-5777.

Sincerely,

A handwritten signature in black ink, appearing to read "R. Webster".

RECEIVED


JUL 30 2011

cc: Office of Consumer Advocate
Office of Small Business Advocate

**PA PUBLIC UTILITY COMMISSION
SECRETARY'S BUREAU**

enclosures

PECO Energy Company Quarterly Reliability Report For Period Ending June 30, 2011



August 1, 2011

PECO Energy ("PECO")

Quarterly Reliability Report for the Period Ending June 30, 2011 filed with the Pennsylvania Public Utility Commission.

Submitted per Rulemaking Re: Amending Electric Service, Docket No. L-00030161 Reliability Regulations at 52 Pa.Code Chapter 57

Section 57.195(e)(1) "A description of each major event that occurred during the preceding quarter, including the time and duration of the event, the number of customers affected, the cause of the event and any modified procedures adopted in order to avoid or minimize the impact of similar events in the future."

No Major events occurred during the 2nd quarter.

Section 57.195(e)(2) "Rolling 12-month reliability index values (SAIFI, CAIDI, SAIDI, and if available, MAIFI) for the EDC's service territory for the preceding quarter. The report shall include the data used in calculating the indices, namely the average number of customers served, the number of sustained customer interruptions, the number of customers affected, and the customer minutes of interruption. If MAIFI values are provided, the report shall also include the number of customer momentary interruptions."

PECO Customers	Sustained Customer Interruptions	Sustained Customer Hours	Momentary Customer Interruptions	Sustained Customer Minutes	SAIFI	CAIDI	SAIDI	MAIFI
1,683,989	1,999,354	4,323,166	1,079,619	259,389,980	1.19	130	154	0.64

*Data reflects 12 months ending 06/30/2011

PECO Benchmarks and Rolling 12-Month Standards				
	SAIFI	CAIDI	SAIDI	MAIFI
Benchmark	1.23	112	138	N/A
Rolling 12-Month Standard	1.48	134	198	N/A

SAIFI is currently below the benchmark and standard. CAIDI and SAIDI are currently below the standard but above the benchmark established on May 7, 2004. No benchmark or standard was established for MAIFI.

Section 57.195(e)(3) "Rolling 12-month reliability index values (SAIFI, CAIDI, SAIDI, and if available, MAIFI) and other pertinent information such as customers served, number of interruptions, customer minutes interrupted, number of lockouts, and so forth, for the worst performing 5% of the circuits in the system. An explanation of how the EDC defines its worst performing circuits shall be included."

PECO's worst performing 5% circuits for 2011 were selected based on a weighted score combining customer interruptions, customer hours, SAIFI and SAIDI, due to outages on each circuit in a 12 month period. This measure is oriented toward contributions to system SAIFI, SAIDI and CAIDI, and local areas with high outage frequency or duration. In addition, circuits with a history of repeat appearance on worst performing lists were selectively included in the 5% list.

Worst circuits and the rolling 12-month reliability index values requested are shown in Appendix A.

Section 57.195(e)(4) "Specific remedial efforts taken and planned for the worst performing 5% of the circuits as identified in paragraph (3)."

Remedial efforts taken or planned to date for PECO's worst performing 5% of circuits are shown in Appendix B.

Section 57.195(e)(5) "A Rolling 12-month breakdown and analysis of outage causes during the preceding quarter, including the number and percentage of service outages, the number of customers interrupted, and customer interruption minutes categorized by outage cause such as equipment failure, animal contact, tree related, and so forth. Proposed solutions to identified service problems shall be included."

12 Months Ending June 30, 2011					
Cause	Service Outages	% of Service Outages	Customer Interruptions	% of Customer Interruptions	Customer Minutes
Animal	931	6.7%	28,081	1.4%	2,189,362
Contact/Dig-In	125	0.9%	17,582	0.9%	1,748,725
Equipment Failure	5,011	36.1%	723,566	36.2%	77,650,659
Lightning	529	3.8%	70,809	3.5%	7,976,701
Other	2,510	18.1%	258,973	13.0%	27,686,162
T&S	37	0.3%	59,184	3.0%	3,239,889
Unknown	644	4.6%	102,545	5.1%	13,707,343
Vegetation-Broken/Uprooted	2,271	16.4%	465,103	23.3%	77,356,669
Vegetation-Ingrowth	1,474	10.6%	187,988	9.4%	40,228,294
Vehicles	356	2.6%	85,523	4.3%	7,606,176

*The data supplied is the number of interrupted customers for each interruption event summed for all events, also known as customer interruptions. A customer interrupted by three separate trouble cases represents three customer interruptions, but only one customer interrupted.

The largest contributors to customer interruptions were equipment failure and tree-related interruptions. The leading groups within the equipment failure category were aerial equipment and underground equipment. Most customer interruptions caused by trees came from broken branches and tree trunks or uprooted trees (71% of vegetation outages), as opposed to ingrowth (29% of vegetation outages). PECO has continued with the significant supplemental vegetation management program it began in 2006 to prune or remove trees between cycles of it's regularly scheduled vegetation management program.

Section 57.195(e)(6). “Quarterly and year to date information on progress toward meeting transmission and distribution inspection and maintenance goals /objectives” (For First, Second and Third Quarter reports only).”

Predictive and Preventive Maintenance Program – status as of 6/30/2011					
	2 nd Quarter Tasks		YTD Tasks		2011 Total Planned
	Planned	Complete	Planned	Complete	
Manhole Inspections (Number of manholes inspected)	432	147	464	349	2,197
Circuit Patrol & Thermography (Number of circuits inspected)	840	883	1,504	1,885	1,504
Recloser Inspections (Number of reclosers inspected)	72	117	144	225	288
Center City Network Inspections (Number of maintenance tasks performed (e.g. visual inspection, functional testing))	156	0	314	392	314
T&S Maintenance (Number of maintenance tasks performed (e.g. visual inspection, predictive/diagnostic maintenance, preventive maintenance) for a variety of substation components)	1,065	1,152	1,973	2,326	4,015
T&S Testing (Number of maintenance tasks performed (e.g. calibration, trip test))	436	640	880	1,084	1,622
Totals	3,001	2,939	5,279	6,261	9,940

Vegetation Management Preventive Maintenance Program – status as of 6/30/11					
	2 nd Quarter Miles		YTD Miles		2011 Total Planned
	Planned	Complete	Planned	Complete	
Distribution Lift and Manual Trimming	627	614	1,037	1,038	2,640
Transmission Trimming and Removals	48	50	87	90	200
Totals	675	664	1,124	1,128	2,840

Section 57.195(e)(7). *“Quarterly and year-to-date information on budgeted versus actual transmission and distribution operation and maintenance expenditures in total and detailed by the EDC’S own functional account code or FERC account code as available.” (For first, second and third quarter reports only.)*

\$Millions	Budgeted 2nd Quarter	Actual 2nd Quarter	Budgeted Year-to-Date	Actual Year-to-Date
New Business Connections	\$0.6	\$0.3	\$1.2	\$0.6
Capacity Expansion	\$0.3	\$1.8	\$1.1	\$2.4
System Performance	\$11.4	\$11.1	\$22.2	\$20.9
Facility Relocation	\$0.6	\$0.7	\$1.1	\$0.9
Maintenance	\$37.9	\$41.0	\$77.6	\$83.3
Total	\$50.8	\$54.9	\$103.2	\$108.1

Section 57.195(e)(8). *“Quarterly and year-to-date information on budgeted versus actual transmission and distribution capital expenditures in total and detailed by the EDC’S own functional account code or FERC account code as available.” (For first, second and third quarter reports only.)*

\$Millions	Budgeted 2nd Quarter	Actual 2nd Quarter	Budgeted Year-to-Date	Actual Year-to-Date
New Business Connections	\$11.2	\$9.3	\$22.2	\$16.9
Capacity Expansion	\$24.8	\$19.0	\$58.9	\$52.7
System Performance	\$23.4	\$22.0	\$46.3	\$40.7
Facility Relocation	\$3.7	\$2.9	\$6.7	\$4.1
Maintenance	\$19.3	\$22.6	\$37.5	\$43.8
Total	\$82.4	\$75.8	\$171.6	\$158.2

Section 57.195(e)(9). *“Dedicated staffing levels for transmission and distribution operation and maintenance at the end of the quarter, in total and by specific category (e.g., lineman, technician and electrician).”*

PECO’s full-time trade staff as of June 30th 2011 was as follows:

Aerial Lineman	375
Underground Lineman (Include UTS)	53
Transmission / Substation Mechanics, Operators	103
Energy Technicians	100
Aerial Foreman	64
Underground Foreman (Includes UTS)	17
Transmission / Substation Foreman	31
Total	743

Contact Persons:

J. Coffman
 Director, Engineering
 (215) 841-4201
jearl.coffman@peco-energy.com

Dick Webster
 Director, Rates and Regulatory
 (215) 841-5777
dick.webster@peco-energy.com

Appendix A

Rolling 12- month reliability index values for 5% worst performing circuits

CIRCUIT	CUSTOMERS ON CIRCUIT	12 Month Rolling Circuit SAIFI	12 Month Rolling Circuit CAIDI	12 Month Rolling Circuit SAIDI	12 Month Rolling Circuit MAIFI	12 Month Rolling Customers Interrupted	12 Month Rolling Customer Hours	12 Month Rolling Momentary Customers Interrupted
ABINGTON_004	177	2.38	167	398	2.00	422	1,173	354
BELLEVUE_002	765	4.13	165	681	0.00	3,163	8,685	0
BRADFORD_341	1,592	2.47	139	344	2.64	3,934	9,121	4204
BRADFORD_342	2,270	3.43	73	251	0.62	7,786	9,500	1399
BRADFORD_346	2,311	2.84	176	500	1.20	6,569	19,273	2780
BRADFORD_352	988	3.89	169	658	1.04	3,842	10,840	1028
BRADFORD_353	1,140	2.85	148	421	2.12	3,244	8,005	2417
BRYAN_002	393	3.46	170	590	1.05	1,360	3,862	414
BRYN_MAWR_132	1,106	3.68	229	843	0.00	4,065	15,531	0
BUCKINGHAM_346	2,506	1.52	170	259	1.79	3,809	10,806	4482
BUCKINGHAM_351	1,832	6.01	147	880	0.54	11,003	26,879	987
BUCKINGHAM_352	2,179	1.64	205	335	0.66	3,565	12,154	1428
BUCKINGHAM_353	1,388	4.54	123	557	0.98	6,305	12,878	1357
BURHOLME_014	160	4.02	200	804	0.00	643	2,143	0
BURHOLME_132	853	4.10	58	237	0.52	3,499	3,371	442
BYBERRY_148	1,888	1.45	125	182	1.06	2,741	5,724	1998
BYBERRY_160	1,472	1.57	133	209	0.00	2,310	5,125	0
BYBERRY_173	1,649	1.37	160	219	0.00	2,253	6,005	0
CARMEL_004	579	2.97	167	498	1.00	1,722	4,804	579
CARVER_000	368	4.35	388	1685	0.00	1,600	10,334	0
CEDARBROOK_131	1,015	0.38	384	145	0.00	382	2,448	0
CHICHESTER_137	2,047	3.01	61	182	0.03	6,163	6,221	63
CHURCH_004	455	5.05	109	551	3.44	2,298	4,176	1564
CIVIC_010	245	1.72	185	319	0.00	422	1,302	0
CLAY_342	2,380	5.23	235	1230	2.42	12,450	48,795	5769
CURLY_000	564	4.46	201	897	2.00	2,516	8,436	1126
DOWNINGTOWN_003	982	5.03	68	342	0.00	4,937	5,603	0
DOYLESTOWN_003	696	3.89	166	646	1.00	2,708	7,496	693
DURHAM_002	588	3.15	130	410	1.00	1,851	4,018	588
EAGLE_352	1,588	5.03	92	463	1.48	7,986	12,264	2355
FALLS_011	323	0.55	136	75	0.00	178	402	0
FALLS_341	986	2.42	218	527	0.52	2,382	8,668	517
FIN_002	451	5.39	159	854	1.04	2,430	6,420	471
FLINT_131	451	2.09	166	347	0.00	944	2,611	0
FLINT_147	162	3.52	457	1608	0.52	570	4,341	84
FOULK_131	1,742	5.04	117	588	1.13	8,788	17,070	1962
FOULK_133	1,472	1.99	106	210	0.00	2,928	5,158	0
FOX_CHASE_131	1,709	3.49	100	350	1.00	5,968	9,966	1709
FOX_CHASE_134	948	3.75	54	202	1.47	3,554	3,196	1396
FURNACE_000	568	5.71	258	1471	0.00	3,242	13,930	0
GLADWYNE_138	478	4.27	233	995	3.01	2,041	7,926	1437
GOLF_001	695	3.15	195	615	5.07	2,191	7,126	3521
GOLF_002	537	4.24	194	822	1.84	2,275	7,361	989
GRAVEL_002	459	3.22	96	310	1.00	1,479	2,372	459
GROVE_000	641	2.82	116	327	2.00	1,808	3,489	1280
HANOVER_003	626	7.45	181	1350	0.17	4,663	14,084	107
HEARTWOOD_001	586	3.38	263	888	0.00	1,978	8,674	0
HOWELL_002	389	8.93	108	961	2.05	3,475	6,234	797

CIRCUIT	CUSTOMERS ON CIRCUIT	12 Month Rolling Circuit SAIFI	12 Month Rolling Circuit CAIDI	12 Month Rolling Circuit SAIDI	12 Month Rolling Circuit MAIFI	12 Month Rolling Customers Interrupted	12 Month Rolling Customer Hours	12 Month Rolling Momentary Customers Interrupted
HUNTING_PARK_048	907	2.31	104	241	0.00	2,093	3,641	0
JARRETT_132	948	1.43	87	124	0.47	1,355	1,961	446
JARRETT_144	1,160	8.20	92	758	0.99	9,516	14,662	1154
JORDAN_002	434	1.67	130	218	1.00	726	1,576	435
LENAPE_000	476	2.25	245	551	0.04	1,070	4,375	21
LINE_131_00WO	545	2.54	262	665	0.00	1,385	6,037	0
LINE_149_00	983	0.99	87	87	2.23	977	1,420	2192
LINE_161_00CO	1,218	1.31	200	262	0.99	1,592	5,309	1200
LINE_175_00CO	338	3.18	139	441	1.00	1,075	2,483	338
LINE_183_00	721	1.03	140	144	0.00	744	1,732	0
LINE_2206	4	1.50	79	119	0.75	6	8	3
LINE_2252	278	2.43	204	496	0.00	676	2,297	0
LINE_2672	70	6.20	70	432	0.00	434	504	0
LINE_2682	1,845	0.40	116	46	0.00	730	1,414	0
LINE_3307NT	1,781	0.38	301	115	0.01	677	3,402	18
LINE_6000	16	4.69	210	984	0.00	75	262	0
LINE_9600	454	3.01	128	384	0.00	1,365	2,904	1
LOMBARD_032	205	3.08	119	366	0.00	632	1,250	0
LOMBARD_043	330	2.95	155	455	0.00	972	2,504	0
MACDADE_136	2,467	0.75	103	77	0.00	1,840	3,147	0
MAIN_000	131	5.42	179	969	0.00	710	2,116	0
MARPLE_003	436	7.22	249	1796	1.00	3,148	13,054	436
MIDDLETOWN_352	2,320	4.73	228	1080	2.27	10,978	41,772	5267
MORGAN_001	246	2.32	131	304	0.00	570	1,246	0
MORGAN_002	370	3.63	267	971	0.00	1,344	5,990	0
MORRISVILLE_012	832	1.37	123	169	0.00	1,142	2,337	0
MORTON_133	781	5.68	243	1379	0.00	4,437	17,955	0
MORTON_142	1,307	3.33	177	589	0.06	4,358	12,826	82
MORWOOD_000	704	3.08	78	241	0.00	2,165	2,830	0
NEW_HOPE_001	515	3.74	187	700	5.99	1,928	6,009	3085
NEW_HOPE_002	705	3.28	156	513	5.99	2,312	6,023	4220
NEWLINVILLE_343	2,517	4.28	57	242	2.98	10,775	10,169	7501
NEWTOWN_SQUAR_131	1,310	4.63	110	508	2.43	6,059	11,101	3182
NEWTOWN_SQUAR_133	683	4.73	212	1004	3.05	3,228	11,428	2085
NEWTOWN_SQUAR_134	658	2.77	88	243	0.38	1,820	2,665	250
NEWTOWN_SQUAR_146	1,150	2.74	98	269	0.88	3,151	5,155	1012
NICE_001	157	5.81	65	378	0.00	912	988	0
NORCO_001	425	3.28	86	283	1.00	1,394	2,005	424
NORTH_WALES_347	851	2.07	96	199	1.54	1,764	2,821	1308
PENCOYD_134	221	4.86	251	1219	0.00	1,074	4,491	0
PIKE_041	1,178	0.90	61	55	0.00	1,059	1,082	0
PLANEBROOK_351	1,238	6.06	152	919	1.70	7,506	18,959	2107
PLUMSTEAD_001	331	4.08	111	453	0.00	1,352	2,498	0
PULASKI_014	966	2.77	92	255	0.23	2,676	4,110	226
ROXBOROUGH_136	1,153	1.36	98	133	0.00	1,573	2,557	0
SCOTT_002	291	2.00	190	379	0.00	581	1,837	0
SHEEDER_000	438	6.21	184	1141	2.99	2,718	8,330	1310
SOLEBURY_002	319	2.50	301	751	2.98	796	3,995	951
SPROUL_002	652	8.37	49	412	2.00	5,454	4,481	1304

CIRCUIT	CUSTOMERS ON CIRCUIT	12 Month Rolling Circuit SAIFI	12 Month Rolling Circuit CAIDI	12 Month Rolling Circuit SAIDI	12 Month Rolling Circuit MAIFI	12 Month Rolling Customers Interrupted	12 Month Rolling Customer Hours	12 Month Rolling Momentary Customers Interrupted
STONY_001	403	3.29	133	437	1.00	1,324	2,938	402
STOTTSVILLE_000	490	5.47	101	553	0.00	2,678	4,515	0
SUNNYBURN_001	458	4.39	249	1095	0.02	2,012	8,362	9
TREDYFFRIN_341	641	3.13	118	369	0.00	2,005	3,943	0
TUNA_141	455	1.84	72	132	0.00	835	1,003	1
UNIVERSITY_011	365	2.96	212	630	0.51	1,082	3,831	186
UPPER_DARBY_132	1,648	3.91	53	206	0.00	6,436	5,670	0
UPPER_MERION_351	2,695	3.41	131	448	0.00	9,198	20,118	0
WAYNE_134	677	4.67	91	425	3.31	3,162	4,793	2242
WAYNE_136	868	2.69	113	304	3.69	2,336	4,402	3203
WEST_BUCK_001	244	2.15	121	261	0.00	525	1,062	0
WHITEMARSH_141	1,045	2.94	78	228	0.80	3,068	3,978	841
WICKER_002	154	3.15	219	691	1.00	485	1,773	154
WOODBOURNE_352	649	1.45	346	500	0.02	938	5,412	12
WRIGHT_000	404	0.45	501	223	0.01	180	1,504	4
WYNCOTE_003	210	6.26	137	858	0.00	1,314	3,005	0
YEADON_134	1,821	1.30	295	382	0.55	2,360	11,605	1010

The data supplied is the number of interrupted customers for each interruption event summed for all events, also known as customer interruptions. If a customer is interrupted by three separate trouble cases, they represent three customer interruptions, but only one customer interrupted.

Appendix B

Remedial efforts taken and planned for 5% worst performing circuits as of 06/30/11

ABINGTON_004

Montgomery County

Completed:

Inspected circuit visually and with thermographic camera
Inspected selected areas of circuit for vegetation issues and corrected as needed
Completed reliability corrective workorders
Completed regularly schedule tree trimming

Planned:

Remedial efforts completed

BELLEVUE_002

Bucks County

Completed:

Inspected circuit visually and with thermographic camera
Inspected selected areas of circuit for vegetation issues and corrected as needed
Completed reliability corrective workorders

Planned:

Remedial efforts completed

BRADFORD_341

Chester County

Completed:

Inspected circuit visually and with thermographic camera
Inspected selected areas of circuit for vegetation issues and corrected as needed
Completed reliability corrective workorders
Installed 3-three phase reclosers

Planned:

Remedial efforts completed

BRADFORD_342

Chester County

Completed:

Inspected circuit visually and with thermographic camera
Inspected selected areas of circuit for vegetation issues and corrected as needed
Installed 2-three phase reclosers

Planned:

Install additional fusing

BRADFORD_346

Chester County

Completed

Completed reliability corrective work orders
Installed animal protection
Tested/Inspected recloser operation
Installed three phase recloser
Upgraded transformer
Installed additional lightning protection
Performed regularly schedule tree clearance
Inspected selected areas of circuit for vegetation issues and corrected as needed
Inspected circuit visually and with thermographic camera
Upgraded fuses

Planned

Remedial efforts completed

BRADFORD_352

Chester County

Completed:

Inspected circuit visually and with thermographic camera
Inspected selected areas of circuit for vegetation issues and corrected as needed
Completed reliability corrective work orders
Inspect/ Test switch operation

Planned

Remedial efforts completed

BRADFORD_353

Chester County

Completed:

Inspected circuit visually and with thermographic camera
Inspected selected areas of circuit for vegetation issues and corrected as needed
Installed three phase recloser
Completed reliability corrective work orders

Planned

Remedial efforts completed

BRYAN_002

York County

Completed:

Completed reliability corrective work orders
Inspected circuit visually and with thermographic camera
Installed additional fuses
Inspected selected areas of circuit for vegetation issues and corrected as needed
Installed lightning protection

Planned:

Remedial efforts completed.

BRYN_MAWR_132

Delaware County

Completed:

Inspected circuit visually and with thermographic camera
Inspected selected areas of circuit for vegetation issues and corrected as needed
Completed reliability corrective work orders

Planned

Remedial efforts completed

BUCKINGHAM_346

Bucks County

Completed:

Inspected circuit visually and with thermographic camera
Inspected selected areas of circuit for vegetation issues and corrected as needed
Completed reliability corrective work orders
Upgraded transformers
Upgraded primary wires
Upgraded underground wires
Install additional lightning protection
Install additional fuses

Planned

Remedial efforts completed

BUCKINGHAM_351

Bucks County

Completed:

Completed reliability corrective work orders
Inspected circuit visually and with thermographic camera
Inspected selected areas of circuit for vegetation issues and correct as needed
Upgraded transformer
Repaired / tested switch operation
Installed additional lightning protection
Installed 3-phase recloser
Performed regularly schedule tree clearance

Planned:

Remedial efforts completed

BUCKINGHAM_352

Bucks County

Completed:

Inspected circuit visually and with thermographic camera
Inspected selected areas of circuit for vegetation issues and corrected as needed
Completed reliability corrective work orders
Upgraded transformer
Inspected/ Tested recloser operation

Planned

Complete reliability corrective work orders

BUCKINGHAM_353

Bucks County

Completed:

Complete reliability corrective work orders
Inspected circuit visually and with thermographic camera
Inspected selected areas of circuit for vegetation issues and corrected as needed
Installed additional lightning protection
Upgraded secondary wires

Planned

Remedial efforts completed

BURHOLME_014

Philadelphia County

Completed:

Inspected circuit visually and with thermographic camera
Inspected selected areas of circuit for vegetation issues and corrected as needed
Tested/ Inspected switch operation
Reconfigure station leg cable
Completed reliability corrective work orders
Replaced cable

Planned

Install switch
Install wildlife protection
Complete reliability corrective work orders

BURHOLME_132

Philadelphia County

Completed:

Inspected circuit visually and with thermographic camera

Inspected selected areas of circuit for vegetation issues and corrected as needed

Completed reliability corrective work orders

Installed additional fuses

Upgraded lightning protection

Installed 3-3 phase reclosers

Planned

Remedial efforts completed

BYBERRY_148

Philadelphia County

Completed:

Inspected circuit visually and with thermographic camera

Inspected selected areas of circuit for vegetation issues and corrected as needed

Completed reliability corrective work orders

Upgrade secondary wires

Upgraded transformer

Install 1 phase recloser

Planned

Remedial efforts completed.

BYBERRY_160

Philadelphia County

Completed:

Inspected circuit visually and with thermographic camera

Inspected selected areas of circuit for vegetation issues and corrected as needed

Completed reliability corrective work orders

Upgraded transformer

Planned

Upgrade fuses

Complete reliability corrective work orders

Upgraded cable insulation

BYBERRY_173

Philadelphia County

Completed:

Completed reliability corrective work orders

Inspected circuit visually and with thermographic camera

Inspected selected areas of circuit for vegetation issues and correct as needed

Installed three phase recloser

Check/ test recloser operation

Installed additional animal protection

Installed compact single phase recloser

Planned:

Remedial efforts completed.

CARMEL_004

Montgomery County

Completed:

Inspected circuit visually and with thermographic camera
Inspected selected areas of circuit for vegetation issues and corrected as needed
Completed reliability corrective work orders
Installed tree wire
Upgraded transformer
Installed additional fuses
Tested recloser operation

Planned

Remedial efforts completed

CARVER_000

Bucks County

Completed:

Inspected circuit visually and with thermographic camera
Inspected selected areas of circuit for vegetation issues and corrected as needed
Completed reliability corrective work orders
Upgraded transformer

Planned

Complete reliability corrective work orders
Install animal protection
Inspect select areas of circuit for vegetation issues and correct as needed

CEDARBROOK_131

Montgomery County

Completed:

Inspected circuit visually and with thermographic camera
Inspected selected areas of circuit for vegetation issues and corrected as needed
Completed reliability corrective work orders
Upgraded secondary wires

Planned

Remedial efforts completed

CHICHESTER_137

Delaware County

Completed:

Inspected circuit visually and with thermographic camera
Inspected selected areas of circuit for vegetation issues and corrected as needed
Completed reliability corrective work orders
Upgraded cable insulation
Upgraded lightning protection
Upgraded secondary wires

Planned

Install 3 phase recloser

CHURCH_004

Delaware County

Completed:

Completed reliability corrective work orders
Inspected circuit visually and with thermographic camera
Inspected selected areas of circuit for vegetation issues and correct as needed
Completed regularly scheduled tree trimming

Planned:

Remedial efforts completed

CIVIC_010

Philadelphia County

Completed:

Completed reliability corrective work orders
Inspected circuit visually and with thermographic camera
Inspected selected areas of circuit for vegetation issues and correct as needed
Replaced underground cable
Upgraded fuse coordination
Completed regularly scheduled tree trimming

Planned:

Remedial efforts completed

CLAY_342

Chester County

Completed:

Completed reliability corrective work orders
Inspected circuit visually and with thermographic camera
Inspected selected areas of circuit for vegetation issues and correct as needed
Installed additional lightning protection
Installed additional fusing
Replaced cable
Installed animal protection
Upgraded wire

Planned:

Check/ test recloser operation

CURLY_000

Bucks County

Completed:

Completed reliability corrective work orders
Inspected circuit visually and with thermographic camera
Inspected selected areas of circuit for vegetation issues and correct as needed

Planned:

Complete reliability corrective work orders

DOWNINGTOWN_003

Chester County

Completed:

Completed reliability corrective work orders
Inspected circuit visually and with thermographic camera
Inspected selected areas of circuit for vegetation issues and correct as needed

Planned:

Remedial efforts completed

DOYLESTOWN_003

Chester County

Completed:

Completed reliability corrective work orders
Inspected circuit visually and with thermographic camera
Inspected selected areas of circuit for vegetation issues and correct as needed

Planned:

Install 3-phase recloser
Upgrade service wire
Inspected selected areas of circuit for vegetation issues and correct as needed

DURHAM_002

Bucks County

Completed:

Completed reliability corrective work orders

Inspected circuit visually and with thermographic camera

Inspected selected areas of circuit for vegetation issues and corrected as needed

Planned

Complete reliability corrective work orders

EAGLE_352

Chester County

Completed:

Completed reliability corrective work orders

Inspected circuit visually and with thermographic camera

Inspected selected areas of circuit for vegetation issues and correct as needed

Install 2- 3 phase reclosers

Complete regularly scheduled tree trimming

Planned:

Remedial efforts completed

FALLS_011

Bucks County

Completed:

Completed reliability corrective work orders

Inspected circuit visually and with thermographic camera

Inspected selected areas of circuit for vegetation issues and correct as needed

Planned:

Remedial efforts completed

FALLS_341

Bucks County

Completed:

Completed reliability corrective work orders

Inspected circuit visually and with thermographic camera

Inspected selected areas of circuit for vegetation issues and correct as needed

Planned:

Remedial efforts completed

FIN_002

York County

Completed

Completed reliability corrective work orders

Inspected circuit visually and with thermographic camera

Upgraded fuses

Inspect selected areas of circuit for vegetation issues and corrected as needed

Planned

Remedial efforts completed

FLINT_131

Delaware County

Completed:

Inspected circuit visually and with thermographic camera

Completed reliability corrective work orders

Performed regularly scheduled tree clearance

Inspected selected areas of circuit for vegetation issues and corrected as needed

Planned:

Remedial efforts completed

FLINT_147

Delaware County

Completed:

Inspected circuit visually and with thermographic camera

Completed reliability corrective work orders

Inspected selected areas of circuit for vegetation issues and corrected as needed

Installed animal protection

Installed additional fuses

Install single phase recloser

Planned:

Remedial efforts completed

FOULK_131

Delaware County

Completed:

Inspected circuit visually and with thermographic camera

Completed reliability corrective work orders

Inspected selected areas of circuit for vegetation issues and corrected as needed

Installed additional lightning protection

Installed additional fuses

Planned:

Install (3) three phase reclosers

FOULK_133

Delaware County

Completed:

Inspected circuit visually and with thermographic camera

Completed reliability corrective work orders

Inspected selected areas of circuit for vegetation issues and corrected as needed

Installed additional fuses

Planned:

Remedial efforts completed

FOX CHASE_131

Philadelphia County

Completed:

Inspected circuit visually and with thermographic camera

Completed reliability corrective work orders

Inspected selected areas of circuit for vegetation issues and correct as needed

Upgrade lightning protection

Install additional fuses

Planned:

Remedial efforts completed

FOX CHASE_134

Philadelphia County

Completed:

Inspected circuit visually and with thermographic camera

Completed reliability corrective work orders

Inspected selected areas of circuit for vegetation issues and correct as needed

Planned:

Install additional fuses

Complete reliability corrective workorders

Replace aerial cable

FURNACE_000

York County

Completed:

Inspected circuit visually and with thermographic camera

Inspected selected areas of circuit for vegetation issues and corrected as needed

Completed reliability corrective work orders

Installed 3 phase recloser

Installed additional fusing

Upgraded fuse coordination

Planned:

Remedial efforts completed

GLADWYNE-138

Delaware County

Completed:

Completed reliability corrective work orders

Inspected selected areas of circuit for vegetation issues and correct as needed

Inspected circuit visually and with thermographic camera

Planned:

Install 3 phase recloser

Complete reliability corrective work orders

GOLF_001

Chester County

Completed:

Completed reliability corrective work orders

Inspected selected areas of circuit for vegetation issues and correct as needed

Inspected circuit visually and with thermographic camera

Installed additional fuses

Planned:

Remedial efforts completed

GOLF_002

Chester County

Completed:

Completed reliability corrective work orders

Inspected selected areas of circuit for vegetation issues and correct as needed

Inspected circuit visually and with thermographic camera

Installed faulted circuit indicators

Installed additional fuses

Planned:

Remedial efforts completed

GRAVEL_002

Bucks County

Completed:

Completed reliability corrective work orders

Inspected selected areas of circuit for vegetation issues and correct as needed

Inspected circuit visually and with thermographic camera

Planned:

Remedial efforts completed

GROVE_000

Chester County

Completed:

Completed reliability corrective work orders

Inspected selected areas of circuit for vegetation issues and correct as needed

Inspected circuit visually and with thermographic camera

Planned:

Complete reliability corrective work orders

Install 2-3phase reclosers on supply circuit

Install additional fuses

HANOVER_003

Bucks County

Completed:

Completed reliability corrective work orders

Upgraded aerial wire

Upgraded transformer

Inspected circuit visually and with thermographic camera

Planned:

Inspect selected areas of circuit for vegetation issues and correct as needed

Complete reliability corrective work orders

HEARTWOOD_001

Bucks County

Completed:

Inspected circuit visually and with thermographic camera

Completed reliability corrective work orders

Planned:

Complete reliability corrective work orders

Install additional fuses

HOWELL_002

Chester County

Completed:

Completed reliability corrective work orders

Inspected selected areas of circuit for vegetation issues and correct as needed

Inspected circuit visually and with thermographic camera

Complete regularly schedule tree trimming

Planned:

Remedial efforts completed

HUNTING_PARK_048

Philadelphia County

Completed:

Completed reliability corrective work orders
Inspected selected areas of circuit for vegetation issues and correct as needed
Inspected circuit visually and with thermographic camera

Planned:

Completed reliability corrective work orders
Install additional lightning protection
Upgrade fusing
Inspect selected areas of circuit for vegetation issues and correct as needed

JARRETT_132

Montgomery County

Completed:

Completed reliability corrective work orders
Inspected selected areas of circuit for vegetation issues and correct as needed
Inspected circuit visually and with thermographic camera

Planned:

Remedial efforts completed

JARRETT_144

Montgomery County

Completed:

Completed reliability corrective work orders
Inspected selected areas of circuit for vegetation issues and correct as needed
Complete regularly schedule tree trimming
Install 2-3 phase reclosers
Upgrade wire

Planned:

Remedial efforts completed

JORDAN_002

Montgomery County

Completed:

Completed reliability corrective work orders
Inspected selected areas of circuit for vegetation issues and correct as needed
Upgraded wires
Upgraded transformers

Planned:

Remedial efforts completed

LENAPE_000

Chester County

Completed:

Inspected selected areas of circuit for vegetation issues and correct as needed
Inspected circuit visually and with thermographic camera
Completed reliability corrective work orders
Install additional fusing

Planned:

Remedial efforts completed

LINE_131-00W0

Bucks County

Completed:

Completed reliability corrective work orders

Inspected selected areas of circuit for vegetation issues and correct as needed

Planned:

Remedial efforts completed

LINE_149_00

Chester County

Completed:

Completed reliability corrective work orders

Inspected selected areas of circuit for vegetation issues and correct as needed

Installed additional lightning protection

Upgrade fuse coordination

Tested/ Inspected switch operation

Installed 3-phase recloser

Planned:

Remedial efforts completed

LINE_161_00CO

Chester County

Completed:

Completed reliability corrective work orders

Inspected selected areas of circuit for vegetation issues and correct as needed

Installed additional lightning protection

Complete regularly scheduled tree trimming

Planned:

Remedial efforts completed

LINE_175_00CO

Chester County

Completed:

Completed reliability corrective work orders

Inspected circuit visually and with thermographic camera

Inspected selected areas of circuit for vegetation issues and corrected as needed

Upgraded secondary wires

Installed lightning protection

Installed 3 phase reclosers

Tested/Inspected switch operation

Perform regularly schedule tree clearance

Planned:

Remedial efforts completed

LINE_183_00

Bucks County

Completed:

Completed reliability corrective work orders

Inspected circuit visually and with thermographic camera

Inspected selected areas of circuit for vegetation issues and correct as needed

Planned:

Remedial efforts completed

LINE_2206

Philadelphia County

Completed:

Completed reliability corrective work orders

Inspected selected areas of circuit for vegetation issues and correct as needed

Inspected circuit visually and with thermographic camera

Upgraded transformer

Installed additional fuses

Upgraded lightning protection

Planned:

Remedial efforts completed

LINE_2252

Philadelphia County

Completed:

Completed reliability corrective work orders

Inspected selected areas of circuit for vegetation issues and correct as needed

Inspected circuit visually and with thermographic camera

Replaced underground cable

Planned:

Remedial efforts completed

LINE_2672

Philadelphia County

Completed:

Completed reliability corrective work orders

Inspected selected areas of circuit for vegetation issues and correct as needed

Inspected circuit visually and with thermographic camera

Planned:

Replace underground cable

LINE_2682

Philadelphia County

Completed:

Completed reliability corrective work orders

Inspected selected areas of circuit for vegetation issues and correct as needed

Inspected circuit visually and with thermographic camera

Upgraded lightning protection

Installed additional fuses

Perform regularly scheduled tree trimming

Planned:

Remedial efforts completed

LINE_3307NT

Chester County

Completed:

Inspected circuit visually and with thermographic camera

Completed reliability corrective work orders

Performed regularly scheduled tree clearance

Installed additional fuses

Installed additional lightning protection

Inspected selected areas of circuit for vegetation issues and corrected as needed

Planned:

Remedial efforts complete

LINE_6000

Bucks County

Completed:

Completed reliability corrective work orders

Inspected selected areas of circuit for vegetation issues and correct as needed

Inspected circuit visually and with thermographic camera

Installed capacitor

Planned:

Remedial efforts completed

LINE_9600

Montgomery County

Completed:

Completed reliability corrective work orders

Inspected selected areas of circuit for vegetation issues and correct as needed

Inspected circuit visually and with thermographic camera

Complete regularly scheduled tree trimming

Planned:

Remedial efforts completed

LOMBARD_032

Philadelphia County

Completed:

Inspected circuit visually and with thermographic camera

Inspected selected areas of circuit for vegetation issues and correct as needed

Completed reliability corrective work orders

Planned:

Install recording /testing devices

LOMBARD_043

Philadelphia County

Completed:

Inspected circuit visually and with thermographic camera

Inspected selected areas of circuit for vegetation issues and correct as needed

Completed reliability corrective work orders

Replaced transformer

Upgraded underground cable

Planned:

Remedial efforts completed

MACDADE_136

Delaware County

Completed:*Inspected circuit visually and with thermographic camera*

Completed reliability corrective work orders

Inspected selected areas of circuit for vegetation issues and correct as needed

Installed animal protection

Completed regularly scheduled tree trimming

Planned

Remedial efforts completed

MAIN_000

Philadelphia County

Completed:

Inspected circuit visually and with thermographic camera

Completed reliability corrective work orders

Inspected selected areas of circuit for vegetation issues and correct as needed

Installed additional fuses

Planned

Reconfigure circuit

Complete regularly scheduled tree trimming

MARPLE_003

Philadelphia County

Completed:

Inspected circuit visually and with thermographic camera

Completed reliability corrective work orders

Inspected selected areas of circuit for vegetation issues and correct as needed

Planned

Remedial efforts completed

MIDDLETOWN_352

Delaware County

Completed:

Performed regularly scheduled tree clearance

Inspected circuit visually and with thermographic camera

Completed reliability corrective work orders

Upgraded cable insulation

Inspected selected areas of circuit for vegetation issues and corrected as needed

Installed additional lightning protection

Installed 3 phase recloser

Performed regularly schedule tree clearance

Installed 3 phase recloser

Planned:

Remedial efforts completed

MORGAN_001

Bucks County

Completed:

Completed reliability corrective work orders

Inspected circuit visually and with thermographic camera

Inspected selected areas of circuit for vegetation issues and correct as needed

Planned

Remedial efforts completed

MORGAN_002

Bucks County

Completed:

Completed reliability corrective work orders

Inspected circuit visually and with thermographic camera

Inspected selected areas of circuit for vegetation issues and correct as needed

Installed additional fuses

Planned

Upgrade wires

MORRISVILLE_012

Bucks County

Completed:

Completed reliability corrective work orders

Inspected circuit visually and with thermographic camera

Inspected selected areas of circuit for vegetation issues and correct as needed

Installed additional lightning protection

Planned

Remedial efforts completed.

MORTON_133

Delaware County

Completed:

Completed reliability corrective work orders

Inspected circuit visually and with thermographic camera

Performed regularly scheduled tree clearance

Installed wildlife protection

Inspected selected areas of circuit for vegetation issues and correct as needed

Completed regularly scheduled tree trimming

Planned

Remedial efforts completed

MORTON_142

Delaware County

Completed

Inspected circuit visually and with thermographic camera

Completed reliability corrective work orders

Performed regularly scheduled tree clearance

Planned:

Complete reliability corrective work orders

MORWOOD_000

Montgomery County

Completed:

Completed reliability corrective work orders

Inspected circuit visually and with thermographic camera

Inspected selected areas of circuit for vegetation issues and correct as needed

Planned

Install additional fuses

Upgrade transformer

NEW_HOPE_001

Bucks County

Completed:

Completed reliability corrective work orders

Inspected selected areas of circuit for vegetation issues and correct as needed

Inspected circuit visually and with thermographic camera

Installed additional fuses

Upgraded transformer

Planned:

Remedial efforts completed

NEW_HOPE_002

Bucks County

Completed:

Completed reliability corrective work orders

Inspected selected areas of circuit for vegetation issues and correct as needed

Inspected circuit visually and with thermographic camera

Upgrade wires

Planned:

Remedial efforts completed

NEWLINVILLE_343

Chester County

Completed:

Completed reliability corrective work orders

Tested/Inspected recloser operation

Inspected circuit visually and with thermographic camera

Upgraded fusing

Installed additional lightning protection

Installed 3 phase recloser

Planned:

Inspect selected areas of circuit for vegetation issues and correct as needed

NEWTOWN_SQUARE_131

Delaware County

Completed:

Completed reliability corrective work orders

Tested/Inspected recloser operation

Inspected circuit visually and with thermographic camera

Inspected selected areas of circuit for vegetation issues and correct as needed

Upgraded fuse coordination

Installed compact 1 phase recloser

Installed 2 - 3 phase reclosers

Installed tree resistant spacer cable

Installed additional animal protection

Planned:

Remedial efforts completed

NEWTOWN_SQUARE_133

Delaware County

Completed:

Inspected circuit visually and with thermographic camera

Completed reliability corrective work orders

Inspected selected areas of circuit for vegetation issues and corrected as needed

Installed additional transformer

Planned:

Remedial efforts completed

NEWTOWN_SQUARE_134

Delaware County

Completed:

Completed reliability corrective work orders

Inspected circuit visually and with thermographic camera

Installed 3 phase reclosers

Planned:

Complete reliability corrective work orders

Install additional fuses

NEWTOWN_SQUARE_146

Delaware County

Completed:

Completed reliability corrective work orders

Inspected circuit visually and with thermographic camera

Inspected selected areas of circuit for vegetation issues and correct as needed

Replaced underground cable

Updated recloser communication settings.

Planned

Remedial efforts completed

NICE_001

Philadelphia County

Completed:

Completed reliability corrective work orders

Inspected circuit visually and with thermographic camera

Inspected selected areas of circuit for vegetation issues and correct as needed

Installed additional fuses

Planned:

Remedial efforts completed

NORCO_001

Chester County

Completed:

Completed reliability corrective work orders

Inspected circuit visually and with thermographic camera

Installed additional fuses

Inspected selected areas of circuit for vegetation issues and correct as needed

Planned

Remedial efforts completed

NORTH_WALES_347

Montgomery County

Completed:

Completed reliability corrective work orders

Inspected circuit visually and with thermographic camera

Installed switch

Planned:

Remedial efforts completed

PENCOYD_134

Delaware County

Completed:

Inspected circuit visually and with thermographic camera

Inspected selected areas of circuit for vegetation issues and correct as needed

Completed reliability corrective work orders

Upgraded transformer

Completed regularly scheduled tree trimming

Planned:

Remedial efforts completed

PIKE_041

Philadelphia County

Completed:

Completed reliability corrective work orders
Inspected circuit visually and with thermographic camera
Upgraded lightning protection
Installed additional fuses

Planned:

Remedial efforts completed

PLANEBROOK_351

Chester County

Completed

Completed reliability corrective work orders
Inspected circuit visually and with thermographic camera
Install additional animal protection
Tested/Inspected recloser operation
Repair switch

Planned

Completed reliability corrective work orders

PLUMSTEAD_001

Bucks County

Completed:

Completed reliability corrective work orders
Inspected circuit visually and with thermographic camera
Inspected selected areas of circuit for vegetation issues and correct as needed

Planned:

Remedial efforts completed.

PULASKI_014

Philadelphia County

Completed

Completed reliability corrective work orders
Inspected circuit visually and with thermographic camera
Inspected selected areas of circuit for vegetation issues and correct as needed
Installed additional fuses
Complete regularly scheduled tree trimming

Planned:

Remedial efforts completed

ROXBOROUGH_136

Philadelphia County

Completed:

Completed reliability corrective work orders
Inspected circuit visually and with thermographic camera
Inspected selected areas of circuit for vegetation issues and correct as needed
Tested/Inspected recloser operation
Installed additional fuses
Installed 3 phase recloser
Completed regularly scheduled tree trimming

Planned:

Remedial efforts completed

SCOTT_002

Delaware County

Completed:

Inspected circuit visually and with thermographic camera

Inspected selected areas of circuit for vegetation issues and correct as needed

Inspect/Test recloser operation

Completed regularly scheduled tree trimming

Planned:

Remedial efforts completed

SHEEDER_000

Chester County

Completed:

Completed reliability corrective work orders

Inspected selected areas of circuit for vegetation issues and correct as needed

Installed 3 phase recloser

Installed additional fuses

Installed additional transformer

Installed faulted circuit indicators

Completed regularly scheduled tree trimming

Planned:

Remedial efforts completed

SOLEBURY_002

Bucks County

Completed:

Inspected circuit visually and with thermographic camera

Completed reliability corrective work orders

Inspected selected areas of circuit for vegetation issues and correct as needed

Planned:

Remedial efforts completed

SPROUL_002

Delaware County

Completed:

Inspected circuit visually and with thermographic camera

Completed reliability corrective work orders

Inspected selected areas of circuit for vegetation issues and correct as needed

Tested Inspected recloser operation

Replaced switch

Installed additional fuses

Completed regularly scheduled tree trimming

Planned:

Remedial efforts completed

STONY_001

Bucks County

Completed:

Inspected circuit visually and with thermographic camera

Inspected selected areas of circuit for vegetation issues and correct as needed

Completed reliability corrective work orders

Install additional fuses

Planned:

Remedial efforts completed.

STOTTSVILLE_000

Chester County

Completed:

Inspected circuit visually and with thermographic camera

Completed reliability corrective work orders

Install additional fuses

Inspect selected areas of circuit for vegetation issues and correct as needed

Planned:

Remedial efforts completed

SUNNYBURN_001

York County

Completed:

Completed reliability corrective work orders

Inspected circuit visually and with thermographic camera

Inspected selected areas of circuit for vegetation issues and correct as needed

Installed additional lightning protection

Installed additional fuses

Installed three phase recloser on supply circuit

Planned:

Remedial efforts completed

TREDDYFRIN_341

Chester County

Completed:

Completed reliability corrective work orders

Inspected circuit visually and with thermographic camera

Inspected selected areas of circuit for vegetation issues and correct as needed

Upgrade fuse coordination

Install 3 phase recloser

Complete regularly scheduled tree trimming

Planned:

Remedial efforts completed

TUNA_141

Philadelphia County

Completed:

Completed reliability corrective work orders

Inspected circuit visually and with thermographic camera

Inspected selected areas of circuit for vegetation issues and correct as needed

Installed additional fuses

Completed regularly scheduled tree trimming

Planned:

Remedial efforts completed

UNIVERSITY_011

Philadelphia County

Completed:

Completed reliability corrective work orders

Inspected circuit visually and with thermographic camera

Completed regularly scheduled tree trimming

Planned:

Remedial efforts completed

UPPER_DARBY_132

Delaware County

Completed:

Completed reliability corrective work orders
Performed regularly schedule tree clearance
Inspected circuit visually and with thermographic camera
Inspect selected areas of circuit for vegetation issues and correct as needed
Installed 3 phase recloser
Installed additional fuses

Planned:

Remedial efforts completed

UPPER_MERION_351

Montgomery County

Completed:

Completed reliability corrective work orders
Inspected circuit visually and with thermographic camera
Inspected selected areas of circuit for vegetation issues and correct as needed
Test/Inspect recloser operation
Test/Inspect switch operation
Completed regularly scheduled tree trimming

Planned:

Remedial work completed

WAYNE_134

Delaware County

Completed:

Completed reliability corrective work orders
Inspected circuit visually and with thermographic camera
Inspected selected areas of circuit for vegetation issues and correct as needed
Tested / Inspected recloser operation
Installed heavy duty tree wire
Installed 3-1 phase reclosers

Planned:

Remedial efforts completed

WAYNE_136

Delaware County

Completed:

Completed reliability corrective work orders
Inspected circuit visually and with thermographic camera
Installed three phase reclosers
Installed tree resistant spacer cable

Planned:

Remedial efforts completed.

WEST_BUCK_001

Bucks County

Completed

Inspected circuit visually and with thermographic camera
Completed reliability corrective work orders
Installed 3 phase recloser on supply circuit
Upgraded secondary wires

Planned:

Remedial efforts completed

WHITEMARSH_141

Montgomery County

Completed:

Inspected circuit visually and with thermographic camera
Inspected selected areas of circuit for vegetation issues and correct as needed
Completed reliability corrective work orders
Replaced underground cable
Installed compact 1 phase recloser
Installed three phase reclosers
Tested recloser operation
Installed animal protection
Upgrades fusing

Planned:

Remedial efforts completed

WICKER_002

Chester County

Completed:

Completed reliability corrective work orders
Inspected circuit visually and with thermographic camera
Inspected selected areas of circuit for vegetation issues and correct as needed

Planned:

Remedial work completed

WOODBOURNE_352

Bucks County

Completed:

Completed reliability corrective work orders
Inspected circuit visually and with thermographic camera

Planned:

Remedial work completed

WRIGHT_000

Bucks County

Completed

Completed reliability corrective work orders
Inspected selected areas of circuit for vegetation issues and correct as needed
Inspected circuit visually and with thermographic camera
Upgraded transformer

Planned:

Remedial efforts completed

WYNCOTE_003

Montgomery County

Completed

Completed reliability corrective work orders
Inspected selected areas of circuit for vegetation issues and correct as needed
Inspected circuit visually and with thermographic camera
Installed tree wire

Planned:

Remedial efforts completed

YEADON_134

Delaware County

Completed:

Inspected circuit visually and with thermographic camera

Inspected selected areas of circuit for vegetation issues and correct as needed

Completed reliability corrective work orders

Performed regularly schedule tree clearance

Tested/Inspected recloser operation

Upgraded transformer

Installed additional animal protection

Upgraded lightning protection

Planned:

Remedial efforts completed

Appendix C

New Business Connections

This work category includes all the facility work required to add a new customer or to increase the load to an existing customer. The facility work will include the facilities required to directly connect the customer to the system and the upgrade/replacement of any existing facility to serve the requested additional load.

Capacity Expansion

This work category includes only capacity work generated by the system design engineer to prevent system failure and to assure the delivery of voltage as specified in the tariff. The addition of new substations and substation enlargements for future load growth will also be included in this project.

System Performance

This work category includes projects designed to upgrade, modify or improve the performance of the distribution system. Also included in this category are indirect costs in support of all categories and one-time accounting adjustment items.

Facility Relocation

This work category includes all requests for relocation of PECO facilities including municipal as well as customer related relocation requests.

Maintenance

This work category includes work performed to repair and restore equipment to its normal state of operation, along with planned preventive maintenance work such as visual and thermographic inspections and tree trimming around transmission and distribution lines.

Storm Funds

Incremental costs (primarily; overtime, contractors, mutual assistance, and meals) incurred while responding to major storms (storms that meet customer outage and duration criteria).